Tunnel Segment Facility for Alkimos Desalination Plant – Noise and Vibration


Response to - Application form reference 4.1 and 4.2 Prescribed premises infrastructure and Proposed Activities

Vibration

CBE has confirmed that there should be no vibration emission apart from the concrete booth slab, APS will be building this slab independently to avoid the vibration impact and the facility shed slab is separated from the remainder of the site, it won't transfer outside to the site, see below sketch, and referenced drawing.


Sketch 1 – showing the Concrete booth slab is isolated.

Refer drawings X2012-FA-CIV-0003[D] CAROUSEL - DRAINAGE PLAN




Sketch 2 – showing the shed slab is separated from the remainder of the site.

Refer drawings BL-2757-2004 - Kiln 11 Processing Building



The expected vibration from the batching plant based on the historical data from CTP is minimal. In addition, the batch plant foundation is completely isolated from the main shed and proximity slab that would attenuate any vibrations.

Refer to batching plant drawing reference - X2012-FA-STR-0007



Predicted Vibration impact – APS will be using vibratory roller to level the stockyard surface, considering the nearest sensitive receiver is over 300 metes from the stockyard and with reference to recommended minimum working distances from the vibration intensive plant from receiver data as per Table 2-5 below (Data taken from CTP project NSW), the likelihood of human or cosmetic damage impact is negligible.

Table 2-5 Recommended minimum working distances for vibration intensive plant from receiver

Plant Item	Rating/Description	Minimum working distance	
		Cosmetic damage	Human response
Vibratory roller	<50kN (typically 1-2t)	5m	15m to 20m
	<100kN (typically 2-4t)	6m	20m
	<200kN (typically 4-6t)	12m	40m
	<300kN (typically 7-13t)	15m	100m
	>300kN (typically 13-18t)	20m	100m
	>300kN (>18t)	25m	100m
Small hydraulic hammer	300kg – 5 to 12t excavator	2m	7m
Medium hydraulic hammer	900kg – 12 to 18t excavator	7m	23m
Large hydraulic hammer	1600kg – 18 to 14t excavator	22m	73m

Refer vibration report ("21028-NV-RP-7-0 SMW CTP ECPCY GNVIS") for establishment work at CTP Project at NSW for more details.

Below sketch showing distance to the nearest residential area from stockyard



Noise

Noise sources and estimated sound pressure level for ASDP project as given below.

Noise levels have been obtained from a combination of manufacturers' specifications and from data provided by the applicant (Lloyd George Acoustics 2024). Data provided includes recorded noise levels from plant within a segment precast factory located in Sydney, run by Acciona Ferrovial Joint Venture (AFJV) with the same equipment and operation.

Table 1 - Site establishment scenarios and equipment (Operating during Day shift only)

	Phase	Type / size	Estimated Sound pressure Level , dBA	Comments
	Phase Site Establishment Includes:	5t excavator w/ auger and pneumatic post driver Franna Semi-trailer Hiab truck 15,000L water truck Smooth drum roller 815 Compactor 15,000L water truck Grader Truck and dog 20t excavator 12t excavator	pressure Level ,	Not using during night shift
1	General structures installation	30t ADT Concrete pump Concrete agitator 25t excavator 16T Vibratory roller Tipper truck Bobcat 8-wheel bogies 16 Ton forklift		
		8 Ton Forklift 3.5 Ton Forklift Concrete pump Concrete agitator 200t mobile crane EWP	106	

Table 2 - Operational scenarios and equipment

Phas	ee	Type / size	Estimated Sound pressure Level , dBA	Comments
	Precast Yard Operation Includes:	Pan Mixers and Silos-	98	
	 External activities such as concrete batching, crane operations and logistics (product handling and delivery). 	Material loader	104	Not used during night shift
	 Internal activities such as production of the concrete segments. 	Truck and dog deliveries concurrently	106	Not used during night shift
		Truck unloading aggregate	114	Not used during night shift
2		10Ton Gantry crane	91	Not used during night shift
2		5 Ton overhead crane	91	
		Steel Fibre Weighing	106	
		16 Ton forklift		
		8 Ton Forklift	99	
		3.5 Ton Forklift		
		Fixed Vibrators (inside the Carousel)	102	
		Rattle guns (inside the Carousel)	115	Rattle guns will be operated during day shift only, will be replaced by torque wrench or similar during night shift
		Vapor Generator	100 db	
		2 x Gas Bullets	80db	
		Water Recycling Plant	105db	